Lakeshore Telemetry Link: Design Notes (Draft)

1 Timers

The acknowledgement timeout is expected to be 306 ms. The retransmission timer is 804 ms.

Tentatively, the send window is 121 packets. The beam report period is 1,690 ms.

Preliminary estimates put the number of strongest beams reported at 23.

2 Failure Detection

The failure detection parameters, as agreed so far:

Table 1. Failure detection parameters

Parameter	Value	Status
Signal-to-noise threshold	3.5 dB	Agreed
Low signal duration	79 s	Working assumption
Consecutive failed retransmissions	180	Agreed
Heartbeat interval	2,868 ms	Working assumption