Harrow Creek WTP: Equipment Schedules

1 Equipment

The schedules below list the plant's pumps, blowers and valves at their rated points.

Table 1a. Raw water pumps

Raw water pumps	Capacity (gpm)	TDH (ft)	Power (hp)	Speed (rpm)
P-101A	7,824	134.8	292	1,679
P-101B	8,837	62.5	264	1,160
P-101C	7,650	132.1	177	1,657

Table 1b. Process air blowers

Process air blowers	Airflow (scfm)	Pressure (psig)	Power (hp)	Speed (rpm)
B-401	2,837	6.58	49	3,153
B-402	1,632	8.95	57	3,552
B-403	2,164	8.27	70	3,183

Table 2a. Valve schedule (1 of 4)

Valves	Cv	Rating (psi)
V-301	605	141
V-302	3,963	175
V-303	902	185
V-304	2,754	239
V-305	1,939	266

Table 2b. Valve schedule (2 of 4)

Valves	Cv	Rating (psi)
V-306	4,528	295
V-307	4,097	288
V-308	2,756	186
V-309	327	289
V-310	2,033	297

Table 2c. Valve schedule (3 of 4)

Valves	Cv	Rating (psi)
V-311	261	196
V-312	3,115	262
V-313	3,515	199
V-314	1,963	209
V-315	2,388	259

Table 2d. Valve schedule (4 of 4)

Valves	Cv	Rating (psi)
V-316	2,910	125
V-317	2,057	234
V-318	3,786	154
V-319	4,274	238
V-320	2,346	255